



Date of Re-assessment: November 23, 2021

DWS Assessed: Bevan Heights DWS

Date Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
1	Upstream Transmission (Region)	Upstream Water Quality from Niagara Falls WTP	Inadequate disinfection or inadequate chlorine residual	Biological contamination of water	Region monitors at St. Paul Ave. Testing completed in NF at Stanley Ave & Church's Lane	NA	2	3	2	12	No - Under Regional Control	-	-	-
2	Upstream Transmission (Region)	Upstream Water Quality from Niagara Falls WTP	Chemical or physical contamination at water source or at chemical addition	Chemical contamination of water	Region manages treatment process	NA	1	4	4	16	No - Under Regional Control	-	-	-
3	Upstream Transmission (Region- Niagara Falls WTP)	Upstream Water from Niagara Falls WTP through transmission main	Break in transmission main	Insufficient supply of water - all purposes	Double supply (also from DeCew) Second supply coming from St. Catharines (Eastchester) now operational Adequate supply from NF, but concerns that Town may not be able to supply all areas (some at higher pressures)	NA	2	2	1	4	No	-	-	-
4	Upstream Transmission (other Municipalities)	Upstream Water through other Municipalities' systems	Contamination of water through other Municipalities' systems	Biological/chemical contamination	Biological - weekly testing of micro & residual	NA	1	4	4	16	No - Under Regional Control	-	-	-
5	Distribution (Town)	Watermain - distribution, infrastructure (i.e. Watermain break)	General physical failure of watermain due to aging, deterioration	Insufficient supply (all purposes) Biological/chemical contamination	Watermain repair procedure in place: PW-DW-SOP-011-001 No leak detection programs in place. 80% or more PVC/PE - infrastructure	- Minimum essential supplies required in stock - Essential Supplies & Services list for approved suppliers & services (PW-DW-LM-009-001) in emergency situations, with 24 hour numbers on Emergency Contact List (PW-DW-LM-014-001) - Aggressive replacement program, system largely renewed	4	1	3	12	No	-	-	-
6	Distribution (Town)	Watermain - distribution, infrastructure	Biological contamination occurring during regular operations - i.e. biofilms	Biological contamination of water	Flushing program in place (annual): PW-DW-SOP-011-003 Weekly sampling & testing for micro (including HPC) and chlorine residual (PW-DW-SOP-012-001)	NA	1	3	2	6	No	-	-	-



Date of Re-assessment: November 23, 2021

DWS Assessed: Bevan Heights DWS

Date Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
7	Distribution (Town)	Watermain - distribution, infrastructure	General chemical/physical contamination	Chemical contamination of water	Majority of system is constructed in PVC/PE. Flushing program in place (annual) (W-DW-SOP-011-003)	NA	2	3	3	18	No	-	-	-
8	Distribution (Town)	Watermain - distribution, infrastructure	Lead contamination (chemical)	Chemical contamination of water	Period of regulatory relief from community lead testing program. Relatively few incidents of lead in drinking water system	NA	1	2	2	4	No	-	-	-
9	Distribution (Town)	Watermain - distribution, infrastructure	Geological fault - i.e. earthquake	Insufficient supply (all purposes)	No incidents in recent history - any tremors have not been substantial enough to cause damage to the system.	- Minimum essential supplies required in stock	1	1	1	1	No	-	-	-
10	Distribution (Town)	Watermain - distribution, infrastructure	Heat wave	Insufficient supply (all purposes)	Water restriction bylaw in place. Consultation with the Region occurs during summer months re: storage monitoring, etc.	NA	2	2	1	4	No	-	-	-
11	Distribution (Town)	Watermain - commissioning of new watermains	Contamination of water - new connections to distribution system	Biological contamination of water	New connections completed by contractor under supervision of licensed operator. Bacteriological testing completed prior to turning water on. Would not connect main if testing had not passed.	NA	-	-	-	N/A	-	-	-	Watermain not commissioned yet, therefore not applicable.
12	Distribution (Town)	Watermain - distribution, infrastructure	Deep freeze	Frozen services or mains, supply loss	Service thawing machine	one machine in stock - possibility of borrowing from other local municipalities if needed	2	1	2	4	No	-	-	-
13	Distribution (Town)	Watermain - distribution, infrastructure	Extreme weather conditions (tornado, ice storm, flood, etc.)	System failure or loss of access to control valves	Tiger torch, steamer, road plow trucks, backhoes	multiple types of equipment on hand and available contractors	1	2	1	2	No	-	-	-
14	Distribution (Town)	Watermain - distribution, infrastructure	Long term impact of climate change	System failure or inadequacy	multiple transmission feeds and two source water feeds	multiple transmission feeds and valves for isolation	1	2	1	2	No	-	-	-



Date of Re-assessment: November 23, 2021

DWS Assessed: Bevan Heights DWS

Date Reviewed: December 8, 2020

**DWQMS Risk Assessment Threshold = 25**

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
15	Distribution (Town)	Watermain - distribution, infrastructure	Water supply shortfall - drought or other reasons	Insufficient supply for all purposes	multiple transmission feeds and two source water feeds	NA	1	5	1	5	No	-	-	Water restriction options through By-law
16	Distribution (Town)	Repair of watermain	Contamination of water - repair to watermain	Biological contamination of water	Repair completed by staff or by contractor under supervision of licensed operator. Bacteriological testing completed but water is turned on prior to results. Chlorine residual testing completed.	- Minimum essential supplies required in stock	1	3	5	15	Yes	AWWA C651 Niagara Municipalities SOP for Watermain Repairs & MECP Disinfection Procedure	AWWA C651 Niagara Municipalities SOP for Watermain Repairs & MECP Disinfection Procedure	Wherever possible, reinstate main only following receipt of results
17	Distribution (Town)	Cross-connections & backflows	Cross-connections & backflows from industrial, agricultural or multi-storey residential service and new construction source water	Biological or chemical cross-contamination of water	No backflow bylaw in place. System runs at high pressure - reduced potential for negative/low pressure events. Known previous incidents (2 in ~40 years).	NA	2	3	4	24	No	Immediate response to backflow events upon becoming aware of event	Suspected Backflow Event PW-DW-PRO-014-006	Backflow bylaw being drafted. BSI Online contracted for tracking devices and tests
18	Distribution (Town)	Cross-connections & backflows	Cross-connections and/or backflows from residential services (i.e. private interconnections to well or cistern)	Biological or chemical cross-contamination of water	No backflow bylaw in place. System runs at high pressure - reduced potential for negative/low pressure events.	NA	1	3	4	12	No	Immediate response to backflow events upon becoming aware of event	Suspected Backflow Event PW-DW-PRO-014-006	Backflow bylaw being drafted. BSI Online contracted for tracking devices and tests
19	Distribution (Town)	Low Chlorine, for example: dead ends	Stagnant water - low chlorine residuals, bacterial regrowth	Biological contamination of water	Flushing completed annually (more often if required). No recent issues with chlorine residuals. Weekly chlorine residuals checked as well as chlorine samples taken with every microbiological sample	- 3 Chlorine Analyzers, meters calibrated quarterly as per PW-DW-PRO-013-001 - Minimum essential supplies required in stock	4	2	3	24	Yes	Maintain minimum free residual of 0.10 mg/L	Water Sampling of Water Distribution System (PW-DW-SOP-012-001); Annual Watermain Flushing (PW-DW-SOP-011-003)	Critical Control Procedure for Low Chlorine in the Distribution System (PW-DW-SOP-018-001)



Date of Re-assessment: November 23, 2021

DWS Assessed: Bevan Heights DWS

Date Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
20	Distribution (Town)	Water delivery system - filling from hydrants (authorized connections)	Failure of Backflow Prevention devices	Biological or chemical contamination of water	Agricultural/contractor users can rent hookup from Town (meter & BFP) for irrigation during set hours This issue is controlled through the application process	-a procedure to check backflow protection devices (checked annually) - Monthly inspection of both Bulk Water Station	2	3	4	24	No	Program in place Backflow Preventers tested annually (contracted service)	DWQMS Operational Plan (PW-DW-OP-001-001) Section 15: Infrastructure Maintenance, Rehabilitation & Renewal	Inspection during filling Education of customer
21	Distribution (Town)	Watermain - distribution, infrastructure (i.e. Leaks)	Minor physical failure of watermain (i.e. Breaks)	Biological contamination of water	100% of system is constructed in PVC (newer). No leak detection program.	- Minimum essential supplies required in stock	3	2	4	24	No	-	-	-
22	Distribution (Town)	Fire hydrant performance (public and private)	Malfunction of hydrants (leaks, freezing etc)	Water loss, loss of pressure for fire flows	Some self-draining hydrants. Hydrant inspection program in place (monthly during winter, otherwise 20% inspected per year). Includes accessibility - Town digs out hydrants. Town inspects all hydrants (public and private).	- Minimum essential supplies required in stock	5	2	2	20	No	-	-	-
23	Distribution (Town)	Customer linkages - fire sprinkler systems	Cross-contamination from private sprinkler systems	Biological or chemical contamination of water	Backflow preventers required as part of Fire Code	NA	1	3	5	15	No	-	-	-
24	Distribution (Private - downstream)	Customer elements - customer system issues	Lead contamination from private connections (pipes, soldered joints, faucets)	Chemical contamination of water (lead)	No known lead services; lead lines are replaced up to property line as they are found. Property owners are advised to do the same. Procedure for replacement: PW-DW-SOP-011-017 Qualified for regulatory relief for lead sampling.	NA	1	2	2	4	No	-	-	-



Date of Re-assessment: November 23, 2021

DWS Assessed: Niagara-on-the-Lake DWS

Last Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
1	Upstream Transmission (Region)	Upstream Water Quality from St. Catharines WTP	Inadequate disinfection or inadequate chlorine residual	Biological contamination of water	Region samples at Line 2 and at monitoring station at Niagara Stone Road & Anderson Lane - Testing completed in St. Cath - not sure where locations are Notification process in place when WTP experiences problems - not formalized	NA	1	3	2	6	No - Under Regional Control	-	-	-
2	Upstream Transmission (Region)	Upstream Water Quality from St. Catharines WTP	Chemical or physical contamination at water source or at chemical addition	Chemical contamination of water	Region manages treatment process	NA	1	4	4	16	No - Under Regional Control	-	-	-
3	Upstream Transmission (Region)	Upstream Water Quality from Niagara Falls WTP	Inadequate disinfection or inadequate chlorine residual	Biological contamination of water	Region monitors at St. Paul Ave. Testing completed in NF - not sure where locations are	NA	2	3	2	12	No - Under Regional Control	-	-	-
4	Upstream Transmission (Region)	Upstream Water Quality from Niagara Falls WTP	Chemical or physical contamination at water source or at chemical addition	Chemical contamination of water	Region manages treatment process	NA	1	4	4	16	No - Under Regional Control	-	-	-
5	Upstream Transmission (Region- St. Catharines WTP)	Upstream Water from St. Catharines WTP through transmission main	Break in transmission main	Insufficient supply of water - all purposes	Double supply (also from NF) Second supply coming from St. Catharines (Eastchester) now operational Adequate supply from NF	NA	2	2	1	4	No	-	-	-
6	Upstream Transmission (Region- Niagara Falls WTP)	Upstream Water from Niagara Falls WTP through transmission main	Break in transmission main	Insufficient supply of water - all purposes	Double supply (also from DeCew) Second supply coming from St. Catharines (Eastchester) now operational Adequate supply from NF, but concerns that Town may not be able to supply all areas (some at higher pressures)	NA	2	2	1	4	No	-	-	-



Date of Re-assessment: November 23, 2021

DWS Assessed: Niagara-on-the-Lake DWS

Last Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
7	Upstream Storage (Region)	Stored Water - Standpipe or Tower	Animal Intrusion	Biological contamination or physical damage	Region ensures routine inspections are completed. The Region has a security policy in place and standards for fencing and related security equipment	NA	1	3	4	12	No	-	-	-
8	Upstream Storage (Region)	Stored Water - Standpipe or Tower	Sabotage	Biological/chemical contamination or physical damage	Region ensures routine inspections are completed. The Region has a security policy in place and standards for fencing and related security equipment	NA	1	5	5	25	No - Under Regional Control	-	Niagara Region's Emergency Response Plan	-
9	Upstream Transmission (all)	Pressure Reducing Valves in transmission mains	Failure of pressure reducing valves - general	Damage to system & services	Region is increasing maintenance & control of PRVs PRVs monitored through plant (SCADA - Region)	NA	2	2	1	4	No	-	-	-
10	Upstream Transmission (other Municipalities)	Upstream Water through other Municipalities' systems	Contamination of water through other Municipalities' systems	Biological/chemical contamination	Biological - weekly testing of micro & residual	NA	1	4	4	16	No - Under Regional Control	-	-	-
11	Distribution (Town)	Watermain - distribution, infrastructure (i.e. Watermain break)	General physical failure of watermain due to aging, deterioration	Insufficient supply (all purposes) Biological/chemical contamination	Watermain repair procedure in place: PW-DW-SOP-011-001 No leak detection programs in place, 80% or more PVC/PE - infrastructure	- Minimum essential supplies required in stock - Essential Supplies & Services list for approved suppliers & services (PW-DW-LM-009-001) in emergency situations, with 24 hour numbers on Emergency Contact List (PW-DW-LM-014-001) - Aggressive replacement program, system largely renewed	4	1	3	12	No	-	-	-
12	Distribution (Town)	Watermain - distribution, infrastructure	Biological contamination occurring during regular operations - i.e. biofilms	Biological contamination of water	Flushing program in place (annual): PW-DW-SOP-011-003 Weekly sampling & testing for micro (including HPC) and chlorine residual (PW-DW-SOP-012-001)	NA	1	3	2	6	No	-	-	-
13	Distribution (Town)	Watermain - distribution, infrastructure	General chemical/physical contamination	Chemical contamination of water	Majority of system is constructed in PVC/PE. Flushing program in place (annual) (W-DW-SOP-011-003)	NA	2	3	3	18	No	-	-	-



Date of Re-assessment: November 23, 2021

DWS Assessed: Niagara-on-the-Lake DWS

Last Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
14	Distribution (Town)	Watermain - distribution, infrastructure	Lead contamination (chemical)	Chemical contamination of water	Period of regulatory relief from community lead testing program. Relatively few incidents of lead in drinking water system	NA	1	2	2	4	No	-	-	-
15	Distribution (Town)	Watermain - distribution, infrastructure	Geological fault - i.e. earthquake	Insufficient supply (all purposes)	No incidents in recent history - any tremors have not been substantial enough to cause damage to the system.	- Minimum essential supplies required in stock	1	1	1	1	No	-	-	-
16	Distribution (Town)	Watermain - distribution, infrastructure	Heat wave	Insufficient supply (all purposes)	Water restriction bylaw in place. Consultation with the Region occurs during summer months re: storage monitoring, etc.	NA	2	2	1	4	No	-	-	-
17	Distribution (Town)	Watermain - commissioning of new watermains	Contamination of water new connections to distribution system	Biological contamination of water	New connections completed by contractor under supervision of licensed operator. Bacteriological testing completed prior to turning water on. Would not connect main if testing had not passed.	NA	-	-	-	N/A	-	-	-	Watermain not commissioned yet, therefore not applicable.
18	Distribution (Town)	Watermain - distribution, infrastructure	Deep freeze	Frozen services or mains, supply loss	Service thawing machine	one machine in stock - possibility of borrowing from other local municipalities if needed	2	1	2	4	No	-	-	-
19	Distribution (Town)	Watermain - distribution, infrastructure	Extreme weather conditions (tornado, ice storm, flood, etc.)	System failure or loss of access to control valves	Tiger torch, steamer, road plow trucks, backhoes	multiple types of equipment on hand and available contractors	1	2	1	2	No	-	-	-
20	Distribution (Town)	Watermain - distribution, infrastructure	Long term impact of climate change	System failure or inadequacy	multiple transmission feeds and two source water feeds	multiple transmission feeds and valves for isolation	1	2	1	2	No	-	-	-
21	Distribution (Town)	Watermain - distribution, infrastructure	Water supply shortfall - drought or other reasons	Insufficient supply for all purposes	multiple transmission feeds and two source water feeds	NA	1	5	1	5	No	-	-	Water restriction options through By-law



Date of Re-assessment: November 23, 2021

DWS Assessed: Niagara-on-the-Lake DWS

Last Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
22	Distribution (Town)	Repair of watermain	Contamination of water repair to watermain	Biological contamination of water	Repair completed by staff or by contractor under supervision of licensed operator. Bacteriological testing completed but water is turned on prior to results. Chlorine residual testing completed.	- Minimum essential supplies required in stock	1	3	5	15	Yes	AWWA C651 Niagara Municipalities SOP for Watermain Repairs & MECP 2020 Disinfection Procedure	AWWA C651 Niagara Municipalities SOP for Watermain Repairs & MECP 2020 Disinfection Procedure	Wherever possible, reinstate main only following receipt of results
23	Distribution (Town)	Cross-connections & backflows	Cross-connections & backflows from industrial, agricultural or multi-storey residential service and new construction source water	Biological or chemical cross-contamination of water	No backflow bylaw in place. System runs at high pressure - reduced potential for negative/low pressure events. Known previous incidents (2 in ~40 years).	NA	2	3	4	24	Yes	Immediate response to backflow events upon becoming aware of event	Suspected Backflow Event PW-DW-PRO-014-006	Backflow bylaw being drafted. BSI Online contracted for tracking devices and tests
24	Distribution (Town)	Cross-connections & backflows	Cross-connections and/or backflows from residential services (i.e. private interconnections to well or cistern)	Biological or chemical cross-contamination of water	No backflow bylaw in place. System runs at high pressure - reduced potential for negative/low pressure events.	NA	1	3	4	12	Yes	Immediate response to backflow events upon becoming aware of event	Suspected Backflow Event PW-DW-PRO-014-006	Backflow bylaw being drafted. BSI Online contracted for tracking devices and tests
25	Distribution (Town)	Low Chlorine, for example: dead ends	Stagnant water - low chlorine residuals, bacterial regrowth	Biological contamination of water	Flushing completed annually (more often if required). No recent issues with chlorine residuals. Weekly chlorine residuals checked as well as chlorine samples taken with every microbiological sample	- 3 Chlorine Analyzers, meters calibrated quarterly as per PW-DW-PRO-013-001 - Minimum essential supplies required in stock	4	2	3	24	Yes	Maintain minimum free residual of 0.10 mg/L	Water Sampling of Water Distribution System (PW-DW-SOP-012-001); Annual Watermain Flushing (PW-DW-SOP-011-003)	Critical Control Procedure for Low Chlorine in the Distribution System (PW-DW-SOP-018-001)



Date of Re-assessment: November 23, 2021

DWS Assessed: Niagara-on-the-Lake DWS

Last Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
26	Distribution (Town)	Water delivery system - filling from hydrants (authorized connections)	Failure of Backflow Prevention devices	Biological or chemical contamination of water	Agricultural/contractor users can rent hookup from Town (meter & BFP) for irrigation during set hours This issue is controlled through the application process	-a procedure to check backflow protection devices (checked annually) - Monthly inspection of both Bulk Water Station	2	3	4	24	No	Program in place Backflow Preventers tested annually (contracted service)	DWQMS Operational Plan (PW-DW-OP-001-001) Section 15: Infrastructure Maintenance, Rehabilitation & Renewal	Inspection during filling Education of customer
27	Distribution (Town)	Water delivery system - Water Station - Town-owned bulk water stations	Failure of Backflow Prevention devices	Biological or chemical contamination of water	Two stations: overhead fill (air gap), Backflow preventers installed Annual inspection of BFPs		1	3	4	12	No	-	-	
28	Distribution (Town)	Watermain - distribution, infrastructure (i.e. Leaks)	Minor physical failure of watermain (i.e. Breaks)	Biological contamination of water	80% of system is constructed in PVC/PE (newer). No leak detection program. Some shallow sewers; 90% of sewers are deeper than watermains.	- Minimum essential supplies required in stock	3	2	4	24	No	-	-	-
29	Distribution (Town)	Fire hydrant performance (public and private)	Malfunction of hydrants (leaks, freezing etc)	Water loss, loss of pressure for fire flows	Some self-draining hydrants. Hydrant inspection program in place (monthly during winter, otherwise 20% inspected per year). Includes accessibility - Town digs out hydrants. Town inspects all hydrants (public and private).	- Minimum essential supplies required in stock	5	2	2	20	No	-	-	-
30	Distribution (Town)	Customer linkages - fire sprinkler systems	Cross-contamination from private sprinkler systems	Biological or chemical contamination of water	Backflow preventers required as part of Fire Code	NA	1	3	5	15	No	-	-	



Date of Re-assessment: November 23, 2021

DWS Assessed: Niagara-on-the-Lake DWS

Last Reviewed: December 8, 2020

DWQMS Risk Assessment Threshold = 25

Recognize							Assess				Control			
Element or Process Step			Hazardous Event	Potential Hazard	Current Available Control Measures	Reliability/Redundancy of Equipment	Risk Evaluation				CCP? Yes or No	Critical Control Limits (can be qualitative or quantitative; use appropriate units)	Relevant Procedures	Potential Additional Controls
#	Process Category	Description of Process					Likelihood (1-5)	Consequence (1-5)	Detectability (1-5)	Assessed Risk (L x C x D = 1 - 125)				
31	Distribution (Private - downstream)	Customer elements - customer system issues	Lead contamination from private connections (pipes, soldered joints, faucets)	Chemical contamination of water (lead)	No known lead services; lead lines are replaced up to property line as they are found. Property owners are advised to do the same. Procedure for replacement: PW-DW-SOP-011-017 Qualified for regulatory relief for lead sampling.	NA	1	2	2	4	No			